

The Baikal Neutrino Telescope - Status and Plans

Outline:

- Detection Methods
- The Detectors: NT200 and NT200+
- Physics Results from NT200
 - Diffuse cosmic neutrino search
- The Km3 Baikal Detector Project
 - ("Gigaton Volume Detector")

Ralf Wischnewski

DESY, Zeuthen

- for the Baikal Collaboration -



Poster:

- A prototype acoustic neutrino detector / 0639
- NT200 Physics Results / 1088



30th ICRC, Merida, Mexico, July 2007

The Baikal Collaboration

- Institute of Nuclear Research, Moscow
- Moscow State University
- DESY Zeuthen
- Irkutsk State University
- Nishni Novgorod State Techn. Univ.
- State Marine Techn. Univ. St.Petersburg
- Kurchatov Institute, Moscow
- JINR, Dubna


~45 authors


Project Milestones

- >1983: Site / Water studies;
R&D: large area PMT, underwater technology,
Physics small setups (exotics search)
- 1991: Project NT200 submitted
- 1993: NT36 - the first underwater array operates
- 1998: NT200 commissioned
- 2005 - 2006:
Upgrade to NT200+ completed; operating
- >2006: R&D activity for a Km3 detector in Lake Baikal
("Gigaton Volume Detector")
- ~2010: expected start of Km3 deployment

Baikal








NT200+
=
NT200
+
3 long outer strings

- Height = 210m
- \varnothing = 200m
- Geom. Volume ~ 5 Mton

NEUTRINO TELESCOPE NT-200



$$\text{Height} = 70\text{m}, \varnothing = 42\text{m} \rightarrow V_{\text{inst}} = 10^5 \text{ m}^3$$


- 8 strings
- 192 optical modules
= 96 pairs (coincidence)
- measure Time, Charge
 - $\sigma_T \sim 1 \text{ ns}$
 - dyn. range $\sim 1000 \text{ p.e.}$

Effective area: $1 \text{ TeV} \sim 2000 \text{ m}^2$
 Eff. Shower volume: $10 \text{ TeV} \sim 0.2 \text{ Mt}$
 $1 \text{ PeV} \sim 1 \text{ Mton} !$



Quasar PMT: $d=37\text{cm} (14.6")$


Advantages (1): Ice - Perfect Deployment Platform



- Ice is available for 6-8 winter-weeks/year :
 - Upgrades & maintenance
 - Test & installation of new equipment
 - Operation of surface detectors (EAS, acoustics,...)
 - Electrical winches used for deployment operations
(all connections done dry)


Foto from March, 2005, 4km off-s NT200+ deployment from 1m thick

Advantages (2): Water - Good Optical Properties



Abs. Length: 22 ± 2 m

In-situ measurements
over many years






Scatt. Length ~ 30-50 m
(geom.scat.L.)

Note: IceCube's „effective” (diffusion) scattering is ~30m
→ for Baikal: ~300 - 500m !

In-situ: Verification of Scattering @ large distances

Calibration Laser $\sim 10^{12} - 5 \cdot 10^{13}$ γ/pulse (1 ns)
 $\rightarrow E_{\text{Shower}} \sim 10 - 500$ PeV

- Measure:
 Photon arrival times on Chan13 @187m distance
- Time Jitter = Scattering + Electronics



NT200 - Selected Results


- Low energy phenomena

- Atmospheric neutrinos
- WIMP Neutrinos




- Search for exotic particles

- Relativistic Magnetic monopoles



- High energy phenomena



- Diffuse neutrino flux
- Neutrinos from GRB
- Prompt muons and neutrinos
- Exotic HE muons



Data sample:

1998-2002 (Apr/98-Feb/03)
1038 days

Atmospheric Muon-Neutrinos



Skyplot of NT200 neutrino events / 5 years
(galactic coordinates)

Galactic center
visible 18 hours per day


- Data: 372 upward ν events (1998-2002).
- MC: 385 ev. expected (15%BG).

→ A high statistics neutrino sample

for Point-Source Search, incl. GalCenter. No evidence for non-atmosph. ν's.

$$(N_\mu(>15\text{GeV})/N_\mu(>1\text{GeV}) \sim 1/7)$$

Search for Fast Monopoles ($\beta > 0.8$)



$$N_\gamma(\lambda) = n^2 (g/e)^2 N_{\gamma\mu}(\lambda) = 8300 N_{\gamma\mu}(\lambda) \quad (!!)$$


$$g = 137/2, \quad n = 1.33$$

→ Bright light source, like muons $\sim E_\mu = 10^7 \text{ GeV}$


Monopole selection criteria:

- large hit channel multiplicity: $N_{\text{hit}} > 35 \text{ ch}$
- clearly upward going track

Background : atmospheric muons (downward)




Search for High Energy Diffuse Cascades



Search within non-instrumented volume
below NT200 detector for cascades =
Upward moving light fronts.


Effective Volume vs. Energy



$V_{\text{det}} > 1 \text{ Mton at } 1 \text{ PeV}$

Diffuse Flux Limits

Exp. Limits, model predictions,
and atmospheric ν -BG.



limits given for all-flavors

1:1:1 flavor flux ratio @earth assumed (source 1:2:0)



For a $\gamma=2$ spectrum $\Phi_\nu \sim E^{-2}$ the
Baikal NT200 limit is (20 TeV $< E <$ 50 PeV):
 $E^2 \Phi_\nu < 8.1 \cdot 10^{-7} \text{ GeV cm}^{-2} \text{ s}^{-1} \text{ sr}^{-1}$

Astropart.Phys. 25 (2006) 140

NT200+ sensitivity (\sim Amanda-II)

Amanda-II, this conf.

Exp. ν_μ limits are
multiplied $\times 3$



Neutrinos from Quasar Cores

SS – Stecker, Salamon (91,05)
 SP – Szabo, Protheroe (92)

Neutrinos from Blazars

M pp+p γ - Mannheim (95)
 P p γ - Protheroe (96)
 MPR - Mannheim, Protheroe, Rachen (01)
 SeSi - Semikoz, Sigl, (03)

Model survival factor $n_{90\%}/N_{\text{model}}$

The New Project: A Km³ - size Detector in Lake Baikal ("Gigaton Volume Detector")

A Km3 - Scale Baikal Neutrino Detector

A sparsely instrumented array:


- 1300-1700 OMs
- 90-100 strings, 350m length
- 12-16 OM/string
- string radial distance $\sim 120\text{m}$ *

→ Cascade effective volume for



$$\geq 100 \text{ TeV: } \sim 0.5\text{-}1. \text{ km}^3$$
$$\delta \lg(E) \sim 0.1, \delta \theta_{\text{med}} < 4^\circ$$

→ Muon detection from 10-30TeV


*Toy model (MC optimization in progress)



Km3 Design Studies (in progress)




contained events



Cascades

instrumented volume
 $V=3.5 \cdot 10^8 \text{ m}^3$



Muons

$\langle S \rangle = 0.8 \cdot 10^6 \text{ m}^2$

PMT Selection for Km3

Basic criteria of PM selection is effective sensitivity to Cherenkov light which depends on

Photocathode area \times Quantum efficiency \times Collection efficiency
and Optical Module design (FOV).



Baikal
NT200+

Quasar-370

D \approx 14.6"

Quantum efficiency \approx 0.15



?

Hamamatsu R8055

D \approx 13"

Quantum efficiency \approx 0.20

?

Photonis XP1807

D \approx 12"

Quantum efficiency \approx 0.24



PMT development now is an active field with KM3NET/ BAIKAL-km3/... :


QE >30% , new Smart-PMT designs (QUASAR-like by Photonis/...?), ...

PMT Selection: Underwater Tests (2007)



6 new PMTs installed in April 2007 inside NT200+:

- 4 PM R8055 (Hamamatsu)
- 2 XP1807 (Photonis)

FADC readout for 2xR8055.



Relative effective sensitivities of large area PMs R8055/13", XP1807/12" and Quasar-370/14.6". Laboratory (squares) and in-situ tests (dots).



Prototype String for Km3 Baikal Neutrino Telescope


April 2008:

Installation of a "new technology"
prototype string as part of NT200+


- Investigation and in-situ tests of all basic elements of the future detector:
 - Optical modules
 - DAQ system
 - new cable communications.
- Study of DAQ/Triggering concept for the km3-detector;
e.g. "quasi-local coincidences"
- Comparison of new FADC readout with classical TDC/ADC approach (200MHz).

Prototype
string

NT200+
current status



Km3 Baikal Project



Baikal - Km3: Schedule

- 06-07 R&D, Testing NT200+
- 08 Technical Design
- 08-14 Fabrication (OMs, cables,
 connectors, electronics)
- 10-12 Deployment (0.1 - 0.3) km3
- 13-14 Deployment (0.3 - 0.6) km3
- 15-16 Deployment (0.6 - 0.9) km3

Summary

- The Baikal Neutrino Telescope operates successfully since 1998.
- NT200 : focusing on diffuse HE-neutrino search.
 - HE-diffuse search: A "Mton-detector" with only 100kton geometric volume.
 - Magnetic Monopoles, WIMPs, HE-atm. μ
- NT200+ : is designed for diffuse cosmic ν -search.
 - 4x sensitivity gain; improved vertex, energy + direction for shower.
 - 5 Mton instrumented volume, $V_{\text{eff}} > 10$ Mton at 10 PeV.
- Baikal-Km3 activities started in 2006.
 - Optimal PMT choice & redesign of F/E & trigger electronics.
 - 2008: Deploy prototype km3-string.
Design based on NT200+ experience and in-situ tests.

—

Thank you.

—



Final deployment step for NT200+. April, 2005.